

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
SCHEDULE-B

NAME OF THE WORK: Improvements to drain at 8th main Bhuvaneshwari Nagara Bagalagunte in ward no. 14

Sl. No	Description of work	Unit	Qty	Rate Quoted by Sri. K.Jagadish	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	270.00	76.45	Rupees Seventy Six and Forty Five Paise Only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	48.45	4537.36	Rupees Four Thousand Five Hundred Thirty Seven and Thirty Six Paise Only
3	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications, complete as per the direction of Engineer-in-charge of the work	Sqm	900.00	273.16	Rupees Two Hundred Seventy Three and Sixteen Paise Only
4	Providing and laying in position reinforced cement concrete of design mix M-20 with OPC Cement @320 kgs with 20 mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @0.460 cum with Super Plasticisers @3 lts confirming to IS 9103-1999 reaffirmed -2008, Machine mixed concrete laid in layers not exceeding 15 cms thick, vibrated for all works in laid in foundation for footings, retaining walls return walls, (any thickness) and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	66.05	5603.87	Rupees Five Thousand Six Hundred Three and Eighty Seven Paise Only

Signature of the Contractor

Executive Engineer

5	Providing T.M.T steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. for TMT Bars Fe 500 complete as per the direction of Engineer-in-charge of the work	Tonne	7.04	61394.2	Rupees Sixty One Thousand Three Hundred Ninety Four and Twenty Paise Only
6	Supplying and fixing precast reinforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. complete as per the direction of Engineer-in-charge of the work	Sqm	202.50	1407.2	Rupees One Thousand Four Hundred Seven and Twenty Paise Only
7	Providing & Fixing Precast Solid cement concrete kerb stones Made out of CC 124 with top and bottom width 114 and 165 mm respectively, 400 mm high and 450MM in length finished with CM 1:3 Plastering and Finishing, Cutting including form work curing including cost of all Material, Labour hire charge of Machinery Loading unloading lead & Lift transporting Ex. complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	500.00	291.8	Rupees Two Hundred Ninety One and Eighty Paise Only
8	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per the direction of Engineer-in-charge of the work	RM	270.00	71.06	Rupees Seventy One and Six Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Signature of the Contractor

Executive Engineer